NSF Major Facilities – Earned Value Management Gold Card

JULY 2019



COMPONENTS

- CA = Control Account = WPs + PPs
- MR = Management Reserve is held by NSF
- ODC = Other Direct Costs
- = Performance Measurement Baseline = CAs + UB + SLPPs = BAC PMB
- = Planning Package (far-term activities within a CA) PP
- SLPP = Summary Level Planning Package
- TPC_{NSB} = Total Project Cost (NSB authorized)
- TPCAWD = Award Amount to Recipient (PMB + contingency + profit/fee)
- TPC = Total Project Cost managed by Recipient (PMB + contingency)
- = Undistributed Budget (activities not yet distributed to CA) UB
- = Work Package (near-term, detail-planned activities within a CA) WP

EVMS BASIC COMPONENTS

- Actual Cost AC =
- EV = Earned Value
- = ACWP = Actual Cost of Work Performed = BCWP = Budgeted Cost for Work Performed
- = BCWS = Budgeted Cost for Work Scheduled
- ΡV = Planned Value = Budget at Completion = Σ BCWS = Sum of Budgeted Cost for Work Scheduled BAC
- Estimate at Completion = ACWP + ETC EAC =
- = Estimated cost of remaining work (WR) ETC

VARIANCES

CV 3 = EV - ACBCWP – ACWP = Cost Variance = $SV^3 = EV - PV$ = BCWP – BCWS = Schedule Variance CV% = (EV - AC) / EV =(BCWP-ACWP) / BCWP SV% = (EV - PV) / PV = (BCWP - BCWS) / BCWSVAC = BAC - EAC

OVERALL STATUS

% scheduled	=	PV _{cum} /BAC	= BCWS _{cum} /BAC
% complete	=	EV _{cum} /BAC	= BCWP _{cum} /BAC
% budget spent	=	AC _{cum} /BAC	= ACWP _{cum} /BAC
Work Remaining (WR)	=	BAC – EV _{cum}	= BAC – BCWP _{cum}

PERFORMANCE INDICES (Favorable is >1.0. unfavorable is <1.0)

				abic is + 1.0, anjav	
CPI	=	EV / AC	=	BCWP / ACWP	= Cost Performance Index
SPI	=	EV / PV	=	BCWP / BCWS	= Schedule Performance Index
TCPI _{EAC}	=	WR / (EAC $- AC_{cum}$)	=	EAC-based To Complete Performance Index	

ESTIMATE AT COMPLETION FORMULAE

-			
EAC	=	BAC / CPI _{cum}	= Estimate at Completion (general)
EAC	=	AC _{cum} + WR/CPI _{cum}	= Estimate at Completion (CPI)
EAC	=	AC _{cum} + WR/(CPI _{cum} * SPI _{cum})	= Estimate at Completion (composite)

Notes:

- ¹ If authorized as part of TPC.
- ² During execution, contingency moves into the PMB per change control process.
- ³ Favorable > 0, Unfavorable < 0

- = Cost Variance %
 - = Schedule Variance %
 - = Variance at Completion